

BID SHEET

HAWAIIAN POOLS OF PINELLAS INC.

Pool Construction Costs

Pool shell: Rigid beam coping around pool, deluxe underwater contoured lounge seat. Large steps for easy pool entry.

Pump: High head pump. 1 hp, 5 year manufacturers warranty.

Filter: Deluxe polyester cartridge with 120 sq./ft. of filter area. Turns over (filters) 20,000 gallons in (6) six hours.

Plumbing: All pipes and fittings are commercial grade, heavy duty, schedule 40 PVC. 2" suction, 1-1/2" return dual safety main drains, 1/2" fill line w/anti siphon and automatic pool cleaner suction line.

Automatic Chlorinator: Completely automatic, time tested, with no parts to corrode. Includes start up chemicals.

Vacuum & Test Kit: Includes vacuum hose, deluxe adjustable pole, vacuum head, water test kit, leaf net and wall brush.

Concrete: Three feet of decking around pool with decorative spray deck topping. Choice of color.

Permits: All necessary construction and electrical permits included.

Electrical: Meets or exceeds all code requirements. Includes one GFI (Ground Fault Interrupter) and an automatic 110 volt time clock. Sub panel to accommodate landscape lighting (owner must provide available space for the main panel). SAM Pool Light.

Installation: Pools are installed by our own experienced crew, usually within 3 working days. The concrete and electrical are then installed and inspected within another 12 working days.

Base Price: \$28,475.00

Expansive soil sub base for concrete (sand & gravel): \$1450.00

Perimeter footer for concrete deck: \$975.00

Cantilever pool/6" water line tile: \$2500.00

Rock boulders per plan (approx. 6 tons): \$1500.00

Dolphins spewing water on rock pedestal with control valve: \$950.00

Additional concrete salt finish w/color deck per plan: \$3675.00

Three (3) 110 volt landscape flood lights, nine (9) 110 volt pagoda tiered landscape lights: \$1860

Railroad Tie, garden wall 3 foot high (28 linear feet): \$1800.00

400 Btu heater natural gas w/gas line, insulated cover spa/solar cover pool: \$3800.00

Brick coping spa, 6" waterline tile w/marble spillway: \$2900.00

Spa light (SAL): \$675.00

Pool & spa controls at pool side: \$650.00

Basketball game: N/C

Credit portable spa (remove & haul) <\$1500.00>